

List of pages in this Trip Kit

Trip Kit Index

Airport Information For EGSS

Terminal Charts For EGSS

Revision Letter For Cycle 01-2014

Change Notices

Notebook

General Information

Location: London Gbr
IATA Code: STN
Lat/Long: N51° 53.1' E000° 14.1'
Elevation: 348 ft

Airport Use: Public
Magnetic Variation: 1.1°W

Fuel Types: Jet A-1
Repair Types: Major Airframe, Major Engine
Customs: Yes
Airport Type: IFR
Landing Fee: No
Control Tower: Yes
Jet Start Unit: No
LLWS Alert: No
Beacon: No
Pattern Altitude: 1000 ft AGL

Sunrise: 0806 Z
Sunset: 1604 Z,

Runway Information

Runway: 04
Length x Width: 10003 ft x 151 ft
Surface Type: asphalt
TDZ-Elev: 337 ft
Lighting: Edge, ALS, Centerline, TDZ
Displaced Threshold: 984 ft

Runway: 22
Length x Width: 10003 ft x 151 ft
Surface Type: asphalt
TDZ-Elev: 348 ft
Lighting: Edge, ALS, Centerline, TDZ

Communication Information

ATIS 127.175
ATIS 114.55
Stansted Ground Tower 121.725
Stansted Delivery Tower 121.95
Stansted Tower 125.55
Stansted Tower 123.8
Essex Radar Approach Control 120.625
Stansted Director Radar 136.2

1. GENERAL

1.1. ATIS

ATIS 127.17 114.55

1.2. NOISE ABATEMENT PROCEDURES

1.2.1. GENERAL

The following procedures may at any time be departed from to the extent necessary for avoiding immediate danger or for complying with ATC instructions. Every operator of ACFT using the APT shall ensure at all times that ACFT are operated in a manner calculated to cause the least disturbance practicable in areas surrounding the APT.

Maintain an altitude as high as practicable, avoid overflying Bishop's Stortford and avoid flying over Sawbridgeworth and Stansted Mountfitchet below 2500' and over St Elizabeth's Home (N51 49.8 E000 05.4) below 4000' (Stansted QNH).

1.2.2. REVERSE THRUST

Avoid use of reverse thrust after landing between 2330-0600LT except for safety reasons.

1.2.3. RUN-UP TESTS

Run-up tests are controlled in accordance with instructions issued by Stansted Airport LTD.egss 30-1

1.2.4. NIGHTTIME RESTRICTIONS

Any ACFT which has a noise classification greater than 95.9 EPNdB may not be scheduled to take off or land between 2330-0600LT.

Any ACFT which has a noise classification greater than 98.9 EPNdB may not be scheduled to take off or land between 2300-0700LT.

Any ACFT which has a noise classification greater than 98.9 EPNdB may not take off between 2300-0700LT, except between 2300-2330LT when

- It was scheduled to take-off prior to 2300LT;
- Take-off was delayed for reasons beyond control of the ACFT operator;
- APT authority has not given notice to the ACFT operator precluding take-off.

Any ACFT may not take off or be scheduled to land between 2300-0700LT where the operator of that ACFT has not provided (prior to its take-off or prior to its scheduled landing time as appropriate) sufficient information to enable the APT authority to verify its noise classification.

None of the provisions of this notice shall apply to a take-off or landing which is made in an emergency consisting of an immediate danger to life or health, whether human or animal.

1.3. LOW VISIBILITY PROCEDURES

1.3.1. GENERAL

Pilots will be informed via ATIS or RTF when Low Visibility Procedures are in operation.

1.3.2. ARRIVAL

All appropriate RWY exits are illuminated and pilots should select the first convenient exit. RWY vacated will be assessed as being when the ACFT has passed the last of the alternate yellow and green centerline lights. These lights denote the extent of the LOC sensitive area.

Surface Movement Radar is available to monitor pilot "RWY vacated" reports.

1.3.3. DEPARTURE

ATC will require departing ACFT to use the following CAT II/III holding points:

- RWY 04: G3, H3, K3, L3 or W3;
- RWY 22: Q3, R3 or S3.

1. GENERAL

1.4. SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM

1.4.1. OPERATION OF MODE S TRANSPONDER WHEN ACFT IS ON THE GROUND

ACFT operators should ensure that Mode S transponders are able to operate when ACFT is on the ground.

Flight crew should select XPNDR or the equivalent according to specific installation, AUTO if available, not OFF or STDBY, and the assigned Mode A code from the request for push-back or taxiing, whichever is earlier or after landing, continuously until the ACFT is fully parked on stand.

After parking the Mode A code 2000 must be set before selecting OFF or STDBY.

Flight crew of ACFT equipped with Mode S having an ACFT identification feature should also set the ACFT ident. This setting is the ACFT ident specified in item 7 of the ICAO flight plan. The ACFT ident should be entered from the request for push-back or taxiing, whichever is earlier, through FMS or transponder control panel.

1.5. TAXI PROCEDURES

On TWY J, marshaller required for ACFT under their own power with a wingspan exceeding 170'/51.9m when routing behind stands 25, 45 and 65.

It is pilot's responsibility not to accept clearance for a taxilane centerline or an area not approved for his ACFT type.

TWY D MAX wingspan 170'/51.9m.

Apron A, B, C and Z lines East and West MAX wingspan 125'/38.1m.

Western Apron MAX wingspan 118'/36m.

1.6. PARKING INFORMATION

1.6.1. GENERAL

Stands 50L, 50R, 51L, 51R, 52L, 52R, 53L, 53R, 61L, 61R, 62L, 62R, 63L, 63R, 64L, 64R, 72L, 72R, 73L, 73R, 83L, 83R, 84L, 84R, 85L, 85R, 204R, 204L, 205R, 205L, 213L, 213R, 214L, 214R equipped with AGNIS.

Stands 1, 1L, 1R, 2, 3, 4, 5, 6, 7, 8, 9L, 9C, 9R, 10, 11L, 11R, 12L, 12C, 12R, 13L, 13C, 13R, 14L, 14R, 15, 20, 21, 22, 23L, 23R, 24L, 24R, 25, 30, 31, 32L, 32R, 33L, 34L, 34R, 41, 42L, 43L, 43R, 44L, 44R, 45L, 45R, 65L, 65R, 205, 213, 214 equipped with SAFEDOCK.

On stands 11C, 23C, 24C, 32C, 33C, 33R, 34C, 40, 42C, 42R, 43C, 44C, 50C, 51C, 52C, 61C, 62C, 63C, 70L, 70R, 71L, 71R, 74, 76, 204, 204F marshaller required.

1.6.2. USE OF APU

Fixed Electrical Ground Power (FEGP) must be used whenever available and serviceable.

Use of ACFT Auxiliary Power Units (APUs), and diesel Ground Power Units is subject to strict controls as set out in published airport regulations. Between 0600-2330LT APUs should be shut down as soon as practicable following arrival and not restarted until 10 minutes prior to departure, except when the outside air temperature (as promulgated by ATC) is below +5 C or above +20 C. Between 2331-0559LT, except when immediately prior to departure, APUs may not be run without notification to Stansted Airside Operations +44(0)1279-662478.

1.7. OTHER INFORMATION

Extensive instrument flying in vicinity of APT.

RWY 04 right-hand circuit.

2. ARRIVAL

2.1. NOISE ABATEMENT PROCEDURES

ACFT using the ILS shall not descend below 2000' (Stansted QNH) before intercepting GS nor thereafter fly below it. ACFT approaching RWY 22 or RWY 04 without ILS assistance shall not join the final approach to either RWY at an altitude less than 1850' unless they are propeller ACFT with less than 5700 KGS MTWA, when minimum altitude shall be 1350' and thereafter shall follow a descent path no lower than the approach path normally indicated by the PAPI.

Between 2330-0600 LT all ACFT except propeller ACFT shall not descend below 3000' (Stansted QNH) until it is established on the final approach and less than 10 NM from touchdown. Between 2330-0600LT no propeller ACFT shall descend below 3000' (Stansted QNH) until established on final approach, nor thereafter fly below the approach path indicated by the PAPI.

2.1.1. LOW POWER/LOW DRAG PROCEDURES

ACFT shall conform to low power/low drag approach procedures. Headings and flight levels/altitudes by ATC. Radar Vectors will be given and descent clearance will include an estimate of distance to touchdown. For procedures RWY 22 via LOREL/ASKEY and ABBOT/CASEY STARs further distance information will be given between initial descent clearance and intercept heading to the ILS. On receipt of descent clearance the pilot will descend at the rate he judges will be best suited to the achievement of continuous descent, the object being to join the glidepath at the appropriate height for the distance without recourse to level flight.

Recommended speeds:

Pilots should typically expect the following speed restrictions to be enforced:

- 220 KT from the holding facility during the intermediate approach phase;
- 180 KT on base leg/closing heading to the ILS;
- between 180 KT and 160 KT when first established on the ILS; and
- thereafter 160 KT to D4.0.

These speeds are applied for ATC separation purposes and are mandatory.

In the event of a new (non-speed related) ATC clearance being issued (e.g. an instruction to descend on ILS), pilots are not absolved from a requirement to maintain a previously allocated speed. All speed restrictions are to be flown as accurately as possible. ACFT unable to conform to these speeds should inform ATC and state what speeds will be used. In the interests of accurate spacing, pilots are requested to comply with speed adjustments as promptly as feasible within their own operational constraints, advising ATC if circumstances necessitate a change of speed for ACFT performance reasons.

2.2. CAT II/III OPERATIONS

RWYs 04/22 approved for CAT II/III operations, special aircrew and ACFT certification required.

2. ARRIVAL

2.3. RWY OPERATIONS

2.3.1. "LAND AFTER" PROCEDURE

Normally, only one ACFT is permitted to land or take-off on the RWY-in-use at any one time. However, when the traffic sequence is two successive landing ACFT, the second one may be allowed to land before the first one has cleared the RWY-in-use, providing:

- The RWY is long enough;
- it is during daylight hours;
- the second ACFT will be able to see the first ACFT clearly and continuously until it is clear of the RWY;
- the second ACFT has been warned.

ATC will provide this warning by issuing the second ACFT with the instruction '**Land after... (first ACFT type)**' in place of the usual instruction 'Cleared to land'. Responsibility for ensuring adequate separation between the two ACFT rests with the pilot of the second ACFT.

2.3.2. SPECIAL LANDING PROCEDURE

Special landing procedures may be in force in conditions hereunder, when the use will be as follows:

- When the RWY-in-use is temporarily occupied by other traffic, landing clearance will be issued to an arriving ACFT provided that at the time the ACFT crosses the threshold of the RWY-in-use the following separation distances will exist:
 - **Landing following departure -**
The departing ACFT will be airborne and at least 2000m/1.1 NM from the threshold of the RWY-in-use, or if not airborne, will be at least 2500m/1.35 NM from the threshold of the RWY-in-use.
- Reduced separation distances as follows will be used where both the preceding and succeeding landing ACFT or both the landing and departing ACFT are propeller driven and have a maximum total weight authorized not exceeding 5700 kg:
 - **Landing following departure -**
The departing ACFT will be airborne and at least 1500m/0.8 NM from the threshold, or if not airborne, will be at least 1500m/0.8 NM from the landing threshold. The reduced distances do not apply to those jets which are 5700 kg MTWA or less.
- Conditions of Use
The procedures will be used by DAY only under the following conditions:
 - When the reported meteorological conditions are equal to or better than a visibility of 6 KM and a ceiling of 1000' and the air controller is satisfied that the pilot of the next arriving ACFT will be able to observe continuously the relevant traffic.
 - When both the preceding and succeeding ACFT are being operated in the normal manner. (Pilots are responsible for notifying ATC if they are operating their ACFT in other than the normal manner).
 - When the RWY is dry and free of all precipitants.
 - When the air controller is able to assess the separation either visually or by means of aerodrome traffic monitor.
- When issuing a landing clearance following the application of these procedures ATC will issue the second ACFT with the following instructions:
 - (call sign) after departing
 - (ACFT Type) cleared to land
 - RWY (Designator).

2. ARRIVAL

2.4. TAXI PROCEDURES

ACFT are not to stop on any RWY exit awaiting instructions from Ground. If a landing ACFT cannot contact Ground due to RTF congestion the pilot should fully vacate the RWY and taxi into the first available TWY block. The pilot should then hold position until contact with Ground can be established.

On vacating the RWY, contact ATC, hold position and await taxi instructions.

2.5. OTHER INFORMATION

Continuous descent without RADAR Control:

The distance from D22.5 BKY (IAF via ABBOT) and D33.0 BPK (IAF via CASEY) is compatible with a 3.0° / 5.2% descent profile.

3. DEPARTURE

3.1. SPEED RESTRICTIONS

MAX 250 KT below FL100 unless cleared otherwise. ATC removes limitations by the phrase 'No ATC speed restriction'. This phrase must not be interpreted as relieving the pilot of his responsibility for the observance of any speed-power limitations due to noise abatement procedures.

If unable to comply, notify ATC when requesting start-up.

3.2. NOISE ABATEMENT PROCEDURES

3.2.1. GENERAL

After take-off operate ACFT so that it is at or above 1350' at 6.5 km from start of roll as measured along the departure track and so that it will not cause, more than:

- 94 dBA between 0700-2300LT,
- 89 dBA between 2300-2330LT and between 0600-0700LT,
- 87 dBA between 2330-6000LT

at any noise monitoring terminal.

Jet ACFT maintain a minimum climb gradient of 4% to at least 4000' (0600-2330LT) unless cleared via BKY (in this case maintain 4% to at least 3000'). Between 2330-0600LT maintain a minimum climb gradient of 4% to at least 4000'. The ACFT shall be operated in such a way to ensure progressively decreasing noise levels at points on the ground under the flight path beyond the monitoring terminal.

Noise preferential routing procedures applicable for all jet ACFT and other ACFT with MTWA of more than 5700 KGS are depicted on London Stansted SID charts and on graphic on chart 30-4.


3.2.2. NOISE QUOTA SYSTEM DURING NIGHT (2300-0700LT)

Main restrictions are as follows:

- Night Period (2300-0700LT)
- Night Quota Period (2330-0600LT)

ACFT movements will score against the quota as follows:

Noise Level Band (EPNdB)	QUOTA Count
84 - 86.9	0.25
87 - 89.9	0.5
90 - 92.9	1
93 - 95.9	2
96 - 98.9	4
99 - 101.9	8
more than 101.9	16

*STANSTED Director(R)
136.2ESSEX Radar(APP)
120.62Apt Elev
348'Alt Set: hPa
Trans level: By ATC Trans alt: 6000'**OUTSIDE THE DESIGNATED RADAR MINIMUM ALTITUDE AREA**

The minimum altitude to be allocated by the approach surveillance controller will be either the Minimum Sector Altitude or **1000'** above any fixed obstacles:

- within 5 NM **①** of the aircraft or
- within the sector 15 NM **②** ahead of and within 20° either side of the aircraft's track.

3 NM **①** or 10 NM **②** when the aircraft is within 15 NM of the radar antennae.

PROCEDURE	LOSS OF COMMUNICATION PROCEDURE
INITIAL APPROACH	Continue visually or by means of an appropriate approved final approach aid. If not possible proceed to BKY at 3000' or last assigned level if higher.
INTERMEDIATE AND FINAL APPROACH	Continue visually or by means of an appropriate final approach aid. If not possible follow the Missed Approach Procedure to BKY at 3000' .

ATIS
127.17 114.55Apt Elev
348'Alt Set: hPa Trans level: By ATC Trans alt: 6000'
RADAR vectoring may be used. Acft may be instructed
'direct to' (wpt) following RADAR vectoring.**ABBOT 1B [ABOT1B], ABBOT 1C [ABOT1C]
RNAV ARRIVALS**




TO BE USED BY ACFT APPROVED

FOR RNAV OPERATIONS IN UK AIRSPACE

NON-APPROVED ACFT USE STAR ABBOT 1D ON CHART 30-2B

WHEN BKY VOR OR DME UNSERVICEABLE USE

RNAV STARS CASEY 1B & 1C ON CHART 30-2A


SPEED RESTRICTION
Cross 3 Min before holding
facility at 250 KT or less.
SLP Speed Limit Point**WARNING**
Do not proceed beyond
ABBOT
without ATC clearance.**1** Aircraft will be
instructed by
ATC to fly at the
appropriate FL.Direct distance from ABBOT to:
Stansted Apt 16 NM**HOLDINGS OVER LAPRA**To be used
when BPK
VOR or DME
u/s**DESCENT PLANNING**Pilots should plan for possible descent
clearance as follows:**ABBOT 1B:** BARM (FL260)
DITOB (FL220; +10 NM)
LAPRA (FL120; K250-)
ABBOT (FL80+; FL140-; K220-)**ABBOT 1C:** IDESI (FL220; +15 NM)
IDESI (FL180)
LAPRA (FL120; K250-)
ABBOT (FL80+; FL140-; K220-)**ACTUAL DESCENT CLEARANCE WILL
BE AS DIRECTED BY ATC.****BARKWAY**
D (H) 116.25 BKY
N51 59.4 E000 03.7**ABBOT**
N52 01.0
E000 36.0**BROOKMANS
PARK**
D (H) 117.5 BPK
N51 45.0 W000 06.4**LAMBOURNE**
D (H) 115.6 LAM
N51 38.8 E000 09.1**BARM**
N52 28.7
E002 34.2**ABBOT 1B**
19.8
248°**DITOB**
10 NM
before DITOB
DITOB
N52 17.0 E001 49.5**ABBOT 1C**
28.3
299°**LAPRA**
N52 07.1
E001 12.6**SLP**
N52 07.1
E001 12.6**ABBOT**
N52 01.0
E000 36.0**IDESE**
N51 53.9 E001 53.1

ATIS
127.17 114.55Apt Elev
348'Alt Set: hPa Trans level: By ATC Trans alt: 6000'
RADAR vectoring may be used. Acft may be instructed
'direct to' (wpt) following RADAR vectoring.**CASEY 1B [CASE1B], CASEY 1C [CASE1C]
RNAV ARRIVALS**TO BE USED BY ACFT APPROVED
FOR BRNAV OPERATIONS IN UK AIRSPACE
NON-APPROVED ACFT USE STAR CASEY 1D ON CHART 30-2C
TO BE USED WHEN BKY VOR OR DME UNSERVICEABLE**WARNING**Do not proceed beyond
CASEY
without ATC clearance.**SPEED RESTRICTION**Cross 3 Min before holding
facility at 250 KT or less.


SLP Speed Limit Point

Direct distance from CASEY to:
Stansted Apt 15 NM**DESCENT PLANNING**Pilots should plan for possible descent
clearance as follows:**CASEY 1B:** BARM1 (FL260)
DITOB (FL220; +10 NM)
LAPRA (FL120; K250-) K250-)**CASEY 1C:** IDESI (FL220; +15 NM)
IDESI (FL180)
LAPRA (FL120; K250-) K250-)**CASEY 1D:** IDESI (FL220; +15 NM)
IDESI (FL180)
LAPRA (FL120; K250-) K250-)**ACTUAL DESCENT CLEARANCE WILL
BE AS DIRECTED BY ATC.**BARM1
N52 28.7
E002 34.2CASEY 1B
19.8
10 NM
before DITOBDITOB
N52 17.0 E001 49.5

CASEY 1C


IDESI
N51 53.9 E001 53.1SLP
LAPRA
N52 07.1
E001 12.6CASEY
N52 00.5
E000 35.0FL140
FL80BARM1
N52 28.7
E002 34.2DITOB
N52 17.0
E001 49.5LAPRA
N52 07.1
E001 12.6CASEY
N52 00.5
E000 35.0IDESI
N51 53.9
E001 53.1SLP
LAPRA
N52 07.1
E001 12.6CASEY
N52 00.5
E000 35.0IDESI
N51 53.9
E001 53.1SLP
LAPRA
N52 07.1
E001 12.6CASEY
N52 00.5
E000 35.0IDESI
N51 53.9
E001 53.1SLP
LAPRA
N52 07.1
E001 12.6CASEY
N52 00.5
E000 35.0IDESI
N51 53.9
E001 53.1SLP
LAPRA
N52 07.1
E001 12.6CASEY
N52 00.5
E000 35.0IDESI
N51 53.9
E001 53.1SLP
LAPRA
N52 07.1
E001 12.6CASEY
N52 00.5
E000 35.0IDESI
N51 53.9
E001 53.1SLP
LAPRA
N52 07.1
E001 12.6CASEY
N52 00.5
E000 35.0IDESI
N51 53.9
E001 53.1**HOLDINGS OVER LAPRA**To be used
when BPK
VOR or DME
u/sFL210
FL150FL210
FL150FL210
FL150FL210
FL150FL210
FL150FL210
FL150FL210
FL150

CHANGES: STAR ABBOT 1F established. © JEPPESEN 2002, 2009. ALL RIGHTS RESERVED.

ATIS
127.17 114.55Apt Elev
348'Alt Set: hPa
Trans level: By ATC Trans alt: 6000'CASEY 1D [CASE1D], CASEY 1E [CASE1E]
CASEY 1F [CASE1F] ①
ARRIVALS

TO BE USED WHEN BKY VOR OR DME UNSERVICEABLE

WARNING

Do not proceed beyond
CASEY
without ATC clearance.

SPEED RESTRICTION

Cross SLPs or 3 Min before
holding facility at 250 KT or less.

SLP Speed Limit Point

DESCENT PLANNING

Pilots should plan for possible
descent clearance as follows:

CASEY 1D: 250 KT by CLN.


CASEY 1E, 1F: by ATC.

ACTUAL DESCENT CLEARANCE
WILL BE AS DIRECTED BY ATC.① STAR is to facilitate the transfer
of traffic between terminal holding
facilities and for use only as di-
rected by ATC. Not to be used for
flight planning purposes.

② Positioning flights from EGKK.



③ Aircraft will be instructed by ATC
to fly at the appropriate FL.

CHANGES: None. © JEPPESEN, 2002, 2010. ALL RIGHTS RESERVED.

ATIS
127.17 114.55Apt Elev
348'Alt Set: hPa
Trans level: By ATC Trans alt: 6000'ASKEY 5A [ASKE5A], ASKEY 2L [ASKE2L]
ASKEY 2M [ASKE2M]
ARRIVALS

TO BE USED WHEN BPK VOR OR DME UNSERVICEABLE

WARNING

Do not proceed beyond
ASKEY
without ATC clearance.Aircraft will be instructed by
ATC to fly at the appropriate FL.HOLDING
OVER ASKEY

NOT TO SCALE

SPEED RESTRICTION

Cross SLPs or 3 Min before
holding facility at 250 KT or less.


SLP Speed Limit Point

DESCENT PLANNING


Pilots should plan for possible
descent clearance as follows:ASKEY 2L: FL140 by 10NM before
KENET for flight planning purposes
only.ACTUAL DESCENT CLEARANCE
WILL BE AS DIRECTED BY ATC.

ATIS
127.17 114.55Apt Elev
348'Alt Set: hPa
Trans level: By ATC Trans alt: 6000'LOREL 1B [LORE1B], LOREL 2N [LORE2N]
LOREL 2P [LORE2P]


ARRIVALS

WHEN BPK VOR OR DME UNSERVICEABLE USE
STARS ASKEY 1B, 2N & 2P ON CHART 30-2G

① Aircraft will be instructed by
ATC to fly at the appropriate FL.



HOLDING OVER LOREL



SPEED RESTRICTION

Cross SLPs or 3 Min before
holding facility at 250 KT or less.

■ SLP Speed Limit Point

DESCENT PLANNING

Pilots should plan for possible
descent clearance as follows:

LOREL 1B, 2N: by ATC.


ACTUAL DESCENT CLEARANCE
WILL BE AS DIRECTED BY ATC.

WARNING

Do not proceed beyond
LOREL
without ATC clearance.

Alt Set: hPa
Trans level: By ATC Trans alt: 6000'

TO BE USED WHEN BPK VOR OR DME UNSERVICEABLE



ATC to fly at the appropriate FL.

WESTCOTT
335 WCO
N51 51.2 W000 57.8

MAX 220KT
By ATC
— 093°

FL140
D17/22

ASKEY
(IAF)
N52 00.8
W000 03.2
17

SLP
BOMBO
N51 59.7
W000 23.8

093°

R273°

163°

2.9

004°

BARKWAY
116.25 BKY
N51 59.4 E000 03.7

071°

23

24

356°

WOODLEY
352 WOD
N51 27.2 W000 52.7

ASKEY
1B, 2N

011°

27

HAZEL
N51 00.3 W000 59.1
FL170

FL90

017°

ASKEY 2P

32.6

D

MAA FL170
L 620

MAA FL170
M 185

32

ASKEY 1B

027°

SOUTHAMPTON
113.35 SAM
N50 57.3 W001 20.7

KATHY
N50 31.2 W001 20.0
FL170

L 980

MAA FL170

LAMBOURNE
115.6 LAM
N51 38.8 E000 09.1

HOLDING
OVER ASKEY

163°

D23.4/27

7000'

LAM

R345°

D23.4

NOT TO SCALE

SPEED RESTRICTION
Cross SLPs or 3 Min before
holding facility at 250 KT or less.
SLP Speed Limit Point

DESCENT PLANNING
Pilots should plan for possible

Cross SLPs or 3 Min before
holding facility at 250 KT or less.

SLP Speed Limit Point

Pilots should plan for possible descent clearance as follows:
ASKEY 1B, 2N: by ATC.
ACTUAL DESCENT CLEARANCE WILL BE AS DIRECTED BY ATC.


Do not proceed beyond
ASKEY
without ATC clearance.

Alt Set: hPa
Trans level: By ATC Trans alt: 6000'

WHEN BPK VOR OR DME UNSERVICEABLE USE
STARS ASKEY 4C & 2S

① Aircraft will be instructed by ATC to fly at the appropriate FL.

Do not proceed beyond
LOREL
without ATC clearance.



Pilots should plan for possible descent clearance as follows:
LOREL 4C: FL190 by AVANT.
LOREL 2S: FL180 by BEDEK.
ACTUAL DESCENT CLEARANCE WILL BE AS DIRECTED BY ATC.

Cross SLPs or 3 Min before
holding facility at 250 KT or less.


SLP Speed Limit Point

Alt Set: hPa
Trans level: By ATC Trans alt: 6000'

TO BE USED WHEN BPK VOR OR DME UNSERVICEABLE

① Aircraft will be instructed by ATC to fly at the appropriate FL.

WARNING
Do not proceed beyond
ASKEY
without ATC clearance.



Pilots should plan for possible descent clearance as follows:
ASKEY 4C: FL190 by AVANT.
ASKEY 2S: FL180 by BEDEK.
ACTUAL DESCENT CLEARANCE WILL BE AS DIRECTED BY ATC.

Cross SLPs or 3 Min before
holding facility at 250 KT or less.

SLP Speed Limit Point

Alt Set: hPa
Trans level: By ATC Trans alt: 6000'

WHEN BPK VOR OR DME UNSERVICEABLE USE
STAR ASKEY 2D

SLP Speed Limit Point

BUSTA
N52 05.6 E000 04.1
(LAM R-355/D27.0)

(IAF)
LOREL
N52 00.8 W000 03.2

BARKWAY
D
(H) 116.25 BKY
... ..
N51 59.4 E000 03.7

BROOKMANS
PARK
D
(H) 117.5 BPK
N51 45.0 W000 06.4
SLP

FL200
FL180

VATON
N51 26.1 W000 20.9

LAMBOURNE
D
(H) 115.6 LAM
N51 38.8 E000 09.1

WARNING
Do not proceed beyond
LOREL
without ATC clearance.

OCKHAM
D
(H) 115.3 OCK
N51 18.3 W000 26.8

SOUTHAMPTON
 ^{13}C NMR (CDCl₃) 113.35 SAM
 N50 57.3 W001 20.7

MIDHURST
D
(H) 114.0 MID
N51 03.2 W000 37.5

UM17
FL175

L620
FL175

GIBSO
N50 45.0 W002 31.1

FL270

BEGTO
N50 45.8 W001 14.1

FL210

AVANT
N50 49.2
W000 56.3

FL190

**ACTUAL DESCENT CLEARANCE
WILL BE AS DIRECTED BY ATC.**

ATIS
127.17 114.55Apt Elev
348'Alt Set: hPa
Trans level: By ATC Trans alt: 6000'

ASKEY 2D [ASKE2D]

ARRIVAL


TO BE USED WHEN BPK VOR OR DME UNSERVICEABLE

① Aircraft will be instructed by
ATC to fly at the appropriate FL.


SPEED RESTRICTION

Cross SLPs or 3 Min before
holding facility at 250 KT or less.

■ SLP Speed Limit Point

HOLDING
OVER ASKEYDirect distance from ASKEY to:
Stansted Apt 13 NM

WARNING
Do not proceed beyond
ASKEY
without ATC clearance.



DESCENT PLANNING

Pilots should plan for possible
descent clearance as follows:

FL270 by GIBSO,

FL210 by BEGTO,

FL190 by AVANT.

**ACTUAL DESCENT CLEARANCE
WILL BE AS DIRECTED BY ATC.**


© JEPPESEN, 2007, 2013. ALL RIGHTS RESERVED.

© JEPPESEN, 2007, 2013. ALL RIGHTS RESERVED.

ATIS
127.17 114.55Apt Elev
348'Alt Set: hPa
Trans level: By ATC Trans alt: 6000'

LOREL 4Q [LORE4Q]

ARRIVAL

WHEN BPK VOR OR DME UNSERVICEABLE USE
STAR ASKEY 4QDirect distance
from LOREL to:
Stansted Apt 13 NM

Alt Set: hPa
Trans level: By ATC Trans alt: 6000'

TO BE USED WHEN BPK VOR OR DME UNSERVICEABLE

WARNING
Do not proceed beyond
ASKEY
without ATC clearance.



- 1** Aircraft will be instructed by ATC to fly at the appropriate FL.
- 2** Positioning flights from EGLC and EGKB.
- 3** If directed to hold enroute, MAX 240KT at all levels.

SPEED RESTRICTION
Cross SLPs or 3 Min before
holding facility at 250 KT or less.

 **SLP** Speed Limit Point

DESCENT PLANNING
Pilots should plan for possible
descent clearance as follows:
FL200 by MAY.
**ACTUAL DESCENT CLEARANCE
WILL BE AS DIRECTED BY ATC.**

ATIS
127.17
114.55Apt Elev
348'

Alt Set: hPa Trans level: By ATC Trans alt: 6000'



1. Initial approach procedures are designed for manoeuvring speeds up to 220 KT and assume aircraft can maintain a descent gradient of approximately 300' per NM.

2. WARNING: Procedure contains stepped descent for ATC and airspace requirements. Departure routes cross beneath these procedures. Strict compliance with altitude requirements is essential.

RWY 04 INITIAL APPROACH PROCEDURE
WITHOUT RADAR CONTROL

FROM ABBOT

WHEN BKY IS U/S ROUTES COMMENCE AT CASEY (REFER TO CHART 30-2U)

**FOR FINAL APPROACH
SEE APPROACH CHARTS****ROUTING/ALTITUDE**


Establish holding inbound at FL80, at D22.5 BKY descend on BKY R-087 inbound, cross D15 BKY at 6000', intercept BPK R-045 inbound maintaining 6000' to D18 BPK, descend to 2500', cross D9 BPK at or below 3000', at D5 BPK turn LEFT, 136° track, when passing BPK R-073 turn LEFT, intercept LOC at 2500' and continue ILSDME or LOCDME approach procedure.

ATIS
127.17
114.55Apt Elev
348'

Alt Set: hPa Trans level: By ATC Trans alt: 6000'


1. Initial approach procedures are designed for manoeuvring speeds up to 220 KT and assume aircraft can maintain a descent gradient of approximately 300' per NM.

2. Continuous descent approach should be used whenever practicable unless otherwise instructed by ATC. Procedure design is compatible with 3° descent path from the outbound end of the holding pattern.

RWY 22 INITIAL APPROACH PROCEDURE
WITHOUT RADAR CONTROL**FROM ABBOT****WHEN BKY IS U/S ROUTES COMMENCE AT CASEY (REFER TO CHART 30-2V)****WARNING**

Do not proceed beyond
ABBOT
without ATC clearance.

**FOR FINAL APPROACH
SEE APPROACH CHARTS**

**ROUTING/ALTITUDE**

From the outbound end of the holding at FL80 descend to 6000', intercept BKY R-087 inbound, at D22.5 BKY descend not below 4000', cross D16.5 BKY at 4000', descend to 2500', turn LEFT, intercept LOC and continue ILSDME or LOCDME approach procedure.

ATIS
127.17
114.55Apt Elev
348'


Alt Set: hPa Trans level: By ATC Trans alt: 6000'

1. Initial approach procedures are designed for manoeuvring speeds up to 220 KT and assume aircraft can maintain a descent gradient of approximately 300' per NM.


2. WARNING: Procedure contains stepped descent for ATC and airspace requirements. Departure routes cross beneath these procedures. Strict compliance with altitude requirements is essential.

RWY 04 INITIAL APPROACH PROCEDURE

WITHOUT RADAR CONTROL
FROM CASEY TO ILS



FOR FINAL APPROACH
SEE APPROACH CHARTS




ROUTING/ALTITUDE

Establish holding inbound at FL80, at D33 BPK descend to 6000', continue on BPK R-061 inbound, intercept CLN R-292, cross D30 CLN at 6000', intercept BPK R-045 inbound maintaining 6000' to D18 BPK, descend to 2500', cross D9 BPK at or below 3000', at D5 BPK turn LEFT, 136° track, when passing BPK R-073 turn LEFT, intercept LOC at 2500' and continue ILSDME or LOCDME approach procedure.



RWY 22 INITIAL APPROACH PROCEDURE

WITHOUT RADAR CONTROL

FROM CASEY TO ILS



Do not proceed beyond
CASEY
without ATC clearance.



From the outbound end of the holding at FL80 descend to 6000', intercept BPK R-061 inbound, at D33 BPK descend not below 4000', at D30 BPK turn RIGHT, 285° track, cross ISX 12 DME at 4000', descend to 2500', turn LEFT, intercept LOC and continue ILSDME or LOCDME approach procedure.



ATIS
127.17
114.55Apt Elev
348'

Alt Set: hPa Trans level: By ATC Trans alt: 6000'

1. Initial approach procedures are designed for manoeuvring speeds up to 220 KT and assume aircraft can maintain a descent gradient of approximately 300' per NM.
2. WARNING: Procedure contains stepped descent for ATC and airspace requirements. Departure routes cross beneath these procedures. Strict compliance with altitude requirements is essential.
3. Lowest holding level at LOREL/ASKEY is 7000' (FL equivalent). However, when radar is out of service 6000' may be used by ATC.

RWY 04 INITIAL APPROACH PROCEDURES WITHOUT RADAR CONTROL FROM LOREL/ASKEY (WHEN BPK U/S) TO ILS

FOR FINAL APPROACH
SEE APPROACH CHARTS




ROUTING/ALTITUDE

146° track, commence descent not below 3000', intercept BKY R-196, cross D8 BKY at 3000', descend to 2500', at D12 BKY turn LEFT, intercept LOC at 2500' and continue ILSDME or LOCDME approach procedure.

RWY 22 INITIAL APPROACH PROCEDURES

WITHOUT RADAR CONTROL

FROM LOREL/ASKEY (WHEN BPK U/S) TO ILS



© JEPPESEN, 2009. ALL RIGHTS RESERVED.

*STANSTED
Director (R)
136.2Apt Elev
348'


- Trans level: By ATC Trans alt: 6000'
1. When instructed contact STANSTED Director or LONDON Control.
 2. SIDs include noise preferential routes (refer to 30-4).
 3. Cruising levels will be issued after take-off by STANSTED Director or LONDON Control.
 4. Flights via airways to EGGW are to file a BKY SID as far as BKY and route BKY - BUSTA - LOREL.

BKY 5R
RWY 22 DEPARTURE
FOR AIRCRAFT LEAVING CONTROLLED AIRSPACE VIA BKY
~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED BY ATC

WARNING: Due to interaction with
other routes do not climb above
4000' until instructed by ATC.

WARNING
No turns below **850'**.

AVERAGE TRACK MILEAGE
12 NM to BKY.

**ROUTING/ALTITUDE**

Climb straight ahead to D3.1 ISX (BKY R-159), turn RIGHT, intercept BKY R-171 inbound by D8 BKY, cross D5 BKY at or above 3000' (MAX 4000'), D2 BKY at 4000', then to BKY, turn RIGHT, BKY R-360 to D3 BKY at 4000'.

*STANSTED
Director (R)
136.2


Apt Elev
348'

- Trans level: By ATC Trans alt: 6000'
1. When instructed contact STANSTED Director or LONDON Control.
 2. SIDs include noise preferential routes (refer to 30-4).
 3. Cruising levels will be issued after take-off by STANSTED Director or LONDON Control.
 4. Flights via airways to EGGW are to file a BKY SID as far as BKY and route BKY - BUSTA - LOREL.

BKY 2S
RWY 04 DEPARTURE
FOR AIRCRAFT LEAVING CONTROLLED AIRSPACE VIA BKY
~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED BY ATC

WARNING: Due to interaction with other routes do not climb above 5000' until instructed by ATC.

WARNING
No turns below 850'.



This SID requires a minimum climb gradient of 5.8% up to 3000' for ATM purposes.

Gnd speed-KT	75	100	150	200	250	300
5.8% V/V (fpm)	441	587	881	1175	1468	1762

ROUTING/ALTITUDE

Climb straight ahead to D2 ISED (BKY R-119), turn LEFT, intercept BKY R-102 inbound by D7 BKY, cross D5 BKY at or above 3000' (MAX 5000'), then to D2 BKY, turn RIGHT, intercept BKY R-360 to D3 BKY at 5000', then to D7 BKY.

*STANSTED
Director (R)
136.2Apt Elev
348'

Trans level: By ATC Trans alt: 6000'


1. When instructed contact STANSTED Director or LONDON Control.
2. SIDs include noise preferential routes (refer to 30-4).
3. Cruising levels will be issued after take-off by STANSTED Director or LONDON Control.

**BUZAD 7R [BUZA7R]
RWY 22 DEPARTURE**
~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED BY ATC

WARNING: Due to interaction with
other routes do not climb above
4000' until instructed by ATC.

WARNING
No turns below **850'**.

AVERAGE TRACK MILEAGE
35 NM to BUZAD.

**ROUTING/ALTITUDE**

Climb straight ahead to D3.1 ISX (BKY R-159), turn RIGHT, intercept BKY R-171 inbound by D8 BKY, cross D5 BKY at or above 3000' (MAX 4000'), then to D2 BKY at 4000', turn LEFT, intercept BKY R-264, cross D5 BKY at 4000', then to BUZAD.

© JEPPESEN, 2004, 2013. ALL RIGHTS RESERVED.

LONDON
Control
118.82

Apt Elev
348'

- Trans level: By ATC Trans alt: 6000'
1. When instructed contact LONDON Control or STANSTED Director.
 2. SIDs include noise preferential routes (refer to 30-4).
 3. Cruising levels will be issued after take-off by LONDON Control.
 4. Do not climb above SID levels until instructed by ATC.

CLACTON EIGHT ROMEO (CLN 8R)

RWY 22 DEPARTURE

**~~SPEEDS~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED**

WARNING - STEPPED CLIMB:

Due to interaction with other routes pilots must ensure strict compliance with the specified climb profile unless cleared by ATC.

WARNING

No turns below **850'**.

AVERAGE TRACK MILEAGE

37 NM to CLN.

NOT TO SCALE

Gnd speed-KT	75	100	150	200	250	300
5.5% V/V (fpm)	418	557	835	1114	1392	1671
5% V/V (fpm)	380	506	760	1013	1266	1519
4.8% V/V (fpm)	365	486	729	972	1215	1458


This SID requires minimum climb gradients

- of 5.5% up to 3000', then
- 5% up to 4000', then
- 4.8% up to 5000' for ATC purposes.

1 Aircraft below 195 KT: first turn no further east than 140° track to intercept CLN R-268 inbound by D33 CLN.

ROUTING/ALTITUDE

Climb straight ahead to D1.2 ISX, turn LEFT, intercept CLN R-268 inbound by XIGAR, cross D28 CLN at or above 3000' (MAX 4000'), D21 CLN at 4000', D16 CLN at 5000', D13 CLN at 6000', then to CLN.



LONDON
Control
118.82

Apt Elev
348'

Trans level: By ATC Trans alt: 6000'

1. When instructed contact LONDON Control or STANSTED Director.
2. SIDs include noise preferential routes (refer to 30-4).
3. Cruising levels will be issued after take-off by LONDON Control.
4. Do not climb above SID levels until instructed by ATC.

CLACTON FOUR SIERRA (CLN 4S)

RWY 04 DEPARTURE



**~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED**

WARNING - STEPPED CLIMB:

Due to interaction with other routes pilots must ensure strict compliance with the specified climb profile unless cleared by ATC.

WARNING

No turns below 850'.



Gnd speed-KT	75	100	150	200	250	300
6.9% V/V (fpm)	524	699	1048	1398	1747	2096
5.5% V/V (fpm)	418	557	835	1114	1392	1671
4.4% V/V (fpm)	334	446	668	891	1114	1337
4.2% V/V (fpm)	319	425	638	851	1063	1276

This SID requires a minimum climb gradient

- 6.9% up to 2500', then
- 5.5% up to 3000', then
- 4.4% up to 4000', then
- 4.2% up to 5000' for ATC purposes.


ROUTING/ALTITUDE

Climb straight ahead to D1 ISED (BKY R-125), turn RIGHT, intercept BKY R-116, cross D14 BKY at or above 2500' (MAX 4000'), D17 BKY at or above 3000' (MAX 4000'), intercept CLN R-268 inbound, cross D21 CLN at 4000', D16 CLN at 5000', D13 CLN at 6000', then to CLN.

*STANSTED
Director (R)
136.2Apt Elev
348'

Trans level: By ATC Trans alt: 6000'

1. When instructed contact STANSTED Director or LONDON Control.
2. SIDs include noise preferential routes (refer to 30-4).
3. Cruising levels will be issued after take-off by STANSTED Director or LONDON Control.

CPT 4R
RWY 22 DEPARTURE**~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED BY ATC****WARNING:** Due to interaction with
other routes do not climb above
4000' until instructed by ATC.**WARNING**
No turns below 850'.**AVERAGE TRACK MILEAGE**
76 NM to CPT.**ROUTING/ALTITUDE**

Climb straight ahead to D3.1 ISX (BKY R-159), turn RIGHT, intercept BKY R-171 inbound by D8 BKY, cross D5 BKY at or above 3000' (MAX 4000'), then to D2 BKY at 4000', turn LEFT, intercept BKY R-260, cross D5 BKY at 4000', then to WCO, turn LEFT, intercept CPT R-025 inbound to CPT.

*STANSTED
Director (R)
136.2Apt Elev
348'

Trans level: By ATC Trans alt: 6000'


1. When instructed contact STANSTED Director or LONDON Control.
2. SIDs include noise preferential routes (refer to 30-4).
3. Cruising levels will be issued after take-off by STANSTED Director or LONDON Control.

CPT 2S

RWY 04 DEPARTURE

~~SPEED~~ MAX 250 KT BELOW FL100**UNLESS OTHERWISE AUTHORIZED BY ATC****WARNING:** Due to interaction with other routes do not climb above 5000' until instructed by ATC.**WARNING**

No turns below 850'.

AVERAGE TRACK MILEAGE
76 NM to CPT.

This SID requires a minimum climb gradient of 5.8% up to 3000' for ATM purposes.

Gnd speed-KT	75	100	150	200	250	300
5.8% V/V (fpm)	441	587	881	1175	1468	1762

ROUTING/ALTITUDE

Climb straight ahead to D2 ISED (BKY R-119), turn LEFT, intercept BKY R-102 inbound by D7 BKY, cross D5 BKY at or above 3000' (MAX 5000'), then to BKY at 5000', turn LEFT, BKY R-260 to WCO, turn LEFT, intercept CPT R-025 inbound to CPT.

LONDON Control
118.82Apt Elev
348'

Trans level: By ATC Trans alt: 6000'

1. When instructed contact LONDON Control or STANSTED Director.
2. SIDs include noise preferential routes (refer to 30-4).
3. Cruising levels will be issued after take-off by LONDON Control.
4. Do not climb above SID level until instructed by ATC.

DOVER 7R (DVR 7R)

RWY 22 DEPARTURE

**~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED****WARNING:** Due to interaction with other routes
do not climb above **5000'** until instructed by ATC.
Ensure strict compliance with specified altitudes.**WARNING**No turns below **850'**.BARKWAY
D 116.25 BKY
(H)
N51 59.4 E000 03.7**AVERAGE TRACK MILEAGE**
38 NM to DET.ILS DME
STANSTED
D * (110.5) ISX
(T)
N51 53.2 E000 14.1


D1.2 ISX

**D30 DET**5000'
3000'**D25 DET**

5000'

GAMDO
N51 34.5 E000 23.5DETLING
D 117.3 DET
(H)
N51 18.2 E000 35.8

30

DOVER
D 114.95 DVR
(H)
N51 09.8 E001 21.5

This SID requires minimum climb gradients
of
6.6% up to 3000', then
7.5% up to 5000' for ATC purpose.

Gnd speed-KT	75	100	150	200	250	300
7.5% V/V(fpm)	570	760	1139	1519	1899	2279
6.6% V/V(fpm)	501	668	1003	1337	1671	2005

ROUTING/ALTITUDE

Climb straight ahead to D1.2 ISX, turn LEFT, intercept DET R-335 inbound, cross D30 DET at or above 3000' (MAX 5000'), D25 DET at 5000', then to DET, turn LEFT, intercept DVR R-286 inbound to DVR.

LONDON Control
118.82Apt Elev
348'

Trans level: By ATC Trans alt: 6000'

1. When instructed contact LONDON Control or STANSTED Director.
2. SIDs include noise preferential routes (refer to 30-4).
3. Cruising levels will be issued after take-off by LONDON Control.
4. Do not climb above SID level until instructed by ATC.

DOVER 5S (DVR 5S)

RWY 04 DEPARTURE

**~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED****WARNING:** Due to interaction with other routes
do not climb above **5000'** until instructed by ATC.
Ensure strict compliance with specified altitudes.**WARNING**No turns below **850'**.BARKWAY
D (H) 16.25 BKY
N51 59.4 E000 03.7ILS DME
STANSTED
D (T) * (110.5) ISED
N51 53.2 E000 14.1LAMBOURNE
D (H) 115.6 LAM
N51 38.8 E000 09.1**AVERAGE TRACK MILEAGE**
42 NM to DET.

126° D0.8 ISED

D9 LAM
N51 46.9 E000 15.25000'
3000'D25 DET
5000'GAMDO
N51 34.5 E000 23.5DETLING
D (H) 117.3 DET
N51 18.2 E000 35.8DOVER
D (H) 114.95 DVR
N51 09.8 E001 21.5

This SID requires a minimum climb gradient
of
5.5% up to 5000' for ATC purposes.

Gnd speed-KT	75	100	150	200	250	300
5.5% V/V(fpm)	418	557	835	1114	1392	1671

ROUTING/ALTITUDE

Climb straight ahead to D0.8 ISED (BKY R-126), turn RIGHT, intercept LAM R-026 inbound to D9 LAM at or above 3000' (MAX 5000'), turn LEFT, intercept DET R-335 inbound, cross D25 DET at 5000', then to DET, turn LEFT, intercept DVR R-286 inbound to DVR.

LONDON Control
118.82Apt Elev
348'



Trans level: By ATC Trans alt: 6000'

1. When instructed contact LONDON Control or STANSTED Director.
2. SIDs include noise preferential routes (refer to 30-4).
3. No turns below 850'.

LAMBOURNE THREE ROMEO (LAM 3R)

RWY 22 DEPARTURE

FOR LANDING AT EGLL ONLY

~~SPEED~~ MAX 250 KT BELOW FL100**UNLESS OTHERWISE AUTHORIZED****WARNING:** Due to interaction with
other routes do not climb above
5000' until instructed by ATC.BARKWAY
P116.25 BKY
N51 59.4 E000 03.7**AVERAGE TRACK MILEAGE**
16 NM to LAM.ILS DME
STANSTED
P*(110.5) ISX
N51 53.2 E000 14.1D1.2 ISX
N51 51.7
E000 12.0ROWAN
N51 45.2 E000 15.0
5000'
3000'LAMBOURNE
P115.6 LAM
N51 38.8 E000 09.1**5000'**

This SID requires minimum climb gradients
of
401' per NM (6.6%) up to **3000'**, then
358' per NM (5.9%) up to **5000'** for ATC
purposes.

Gnd speed-KT	75	100	150	200	250	300
401' per NM	501	668	1003	1337	1671	2005
358' per NM	448	597	896	1195	1494	1792

ROUTING/ALTITUDE

Climb straight ahead, at D1.2 ISX turn LEFT, intercept BKY R-156 to ROWAN, cross at or
above 3000' (MAX 5000'), turn RIGHT, intercept LAM R-036 inbound to LAM, cross at 5000'.

LONDON Control
118.82


Apt Elev
348'

Trans level: By ATC Trans alt: 6000'
1. When instructed contact LONDON Control or STANSTED Director.
2. SIDs include noise preferential routes (refer to 30-4).
3. No turns below 850'.

LAMBOURNE TWO SIERRA (LAM 2S)
RWY 04 DEPARTURE
FOR LANDING AT EGLL ONLY
~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED

WARNING: Due to interaction with
other routes do not climb above
5000' until instructed by ATC.

AVERAGE TRACK MILEAGE
20 NM to LAM.



BARKWAY
D 116.25 BKY
N51 59.4 E000 03.7

ILS DME
STANSTED
D * (110.5) ISED
N51 53.2 E000 14.1

LAMBOURNE
D 115.6 LAM
N51 38.8 E000 09.1

D0.8 ISED
N51 54.3
E000 15.9

D9 LAM
5000'
3000'

This SID requires minimum climb gradients
of
334' per NM (5.5%) up to **3000'**, then
280' per NM (4.6%) up to **5000'** for ATC
purposes.

Gnd speed-KT	75	100	150	200	250	300
334' per NM	418	557	835	1114	1392	1671
280' per NM	349	466	699	932	1165	1398

ROUTING/ALTITUDE

Climb straight ahead, at D0.8 ISED (BKY R-126) turn RIGHT, intercept LAM R-027 inbound, cross D9 LAM at or above 3000' (MAX 5000'), then to LAM, cross at 5000'.

LONDON Control
118.82Apt Elev
348'

Trans level: By ATC Trans alt: 6000'

1. When instructed contact LONDON Control or STANSTED Director.
2. SIDs include noise preferential routes (refer to 30-4).
3. Cruising levels will be issued after take-off by LONDON Control.
4. Do not climb above SID level until instructed by ATC.

LYDD 5R (LYD 5R) RWY 22 DEPARTURE


ALSO FOR POSITIONING FLIGHTS TO EGKK ①

~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED

WARNING: Due to interaction with other routes
do not climb above **5000'** until instructed by ATC.
Ensure strict compliance with specified altitudes.

WARNINGNo turns below **850'**.

AVERAGE TRACK MILEAGE
38 NM to DET.



This SID requires minimum climb gradients
of
6.6% up to 3000', then
7.5% up to 5000' for ATC purposes.

Gnd speed-KT	75	100	150	200	250	300
7.5% V/V(fpm)	570	760	1139	1519	1899	2279
6.6% V/V(fpm)	501	668	1003	1337	1671	2005

ROUTING/ALTITUDE

Climb straight ahead to D1.2 ISX, turn LEFT, intercept DET R-335 inbound, cross D30 DET at or above 3000' (MAX 5000'), D25 DET at 5000', then to DET, intercept LYD R-331 inbound to LYD.

LONDON Control
118.82Apt Elev
348'

Trans level: By ATC Trans alt: 6000'

1. When instructed contact LONDON Control or STANSTED Director.
2. SIDs include noise preferential routes (refer to 30-4).
3. Cruising levels will be issued after take-off by LONDON Control.
4. Do not climb above SID level until instructed by ATC.


LYDD FOUR SIERRA (LYD 4S)

RWY 04 DEPARTURE

ALSO FOR POSITIONING FLIGHTS TO EGKK ①

~~SPEED~~ MAX 250 KT BELOW FL100**UNLESS OTHERWISE AUTHORIZED****WARNING:** Due to interaction with other routes do not climb above **5000'** until instructed by ATC. Ensure strict compliance with specified altitudes.**WARNING**No turns below **850'**.

- ① Follow SID to DET, then join TIMBA 3E STAR, maintaining 5000'.



This SID requires a minimum climb gradient of 5.5% up to 5000' for ATC purposes.

Gnd speed-KT	75	100	150	200	250	300
5.5% V/V(fpm)	418	557	835	1114	1392	1671

ROUTING/ALTITUDE

Climb straight ahead to D0.8 ISED (BKY R-126), turn RIGHT, intercept LAM R-026 inbound to D9 LAM at or above 3000' (MAX 5000'), turn LEFT, intercept DET R-335 inbound, cross D25 DET at 5000', then to DET, intercept LYD R-331 inbound to LYD.

LONDON Control
118.82Apt Elev
348'

Trans level: By ATC Trans alt: 6000'

1. When instructed contact LONDON Control or STANSTED Director.
2. SIDs include noise preferential routes (refer to 30-4).
3. No turns below 850'.
4. RNP 1 only available for authorized aircraft.

CLN 1E

RWY 22 RNAV DEPARTURE

RNP 1 (GNSS)

RF REQUIRED

ONLY AVAILABLE TO APPROVED PARTICIPATING ACFT
WHICH ARE EQUIPPED AND OPERATED IN ACCORDANCE
WITH THE REQUIREMENTS OF JAA TGL-10 OR EQUIVALENT
NON-APPROVED ACFT USE CONVENTIONAL SID


**~~SPEED~~ MAX 250 KT BELOW FL 100
UNLESS OTHERWISE AUTHORIZED**

TEMPORARY PROCEDURE
REFER ALSO TO LATEST NOTAMS


TRIAL PROCEDURE

WARNING - STEPPED CLIMB

Due to interaction with other routes pilots must
ensure strict compliance with the specified climb
profile unless cleared by ATC.



NOT TO SCALE

**ROUTING/ALTITUDE**

SSW01 (900' +; K210-) - SSS03 (K210-) - SSE06 (K210-) - SSE11 (3000' +; K250-) -
SSE18 (4000' +; K250-) - SSE23 (5000' +; K250-) - SSE26 (6000' +; K250-) - CLN (K250-).

LONDON Control
118.82Apt Elev
348'

Trans level: By ATC Trans alt: 6000'

1. When instructed contact LONDON Control or STANSTED Director.
2. SIDs include noise preferential routes (refer to 30-4).
3. No turns below 850'.
4. RNP 1 only available for authorized aircraft.

DVR 1D
RWY 04 RNAV DEPARTURE

RNP 1 (GNSS)

RF REQUIRED

ONLY AVAILABLE TO APPROVED PARTICIPATING ACFT
WHICH ARE EQUIPPED AND OPERATED IN ACCORDANCE
WITH THE REQUIREMENTS OF JAA TGL-10 OR EQUIVALENT
NON-APPROVED ACFT USE CONVENTIONAL SID


~~SPEED~~ MAX 250 KT BELOW FL100
UNLESS OTHERWISE AUTHORIZED

TEMPORARY PROCEDURE
REFER ALSO TO LATEST NOTAMS


TRIAL PROCEDURE

WARNING - STEPPED CLIMB

Due to interaction with other routes pilots must
ensure strict compliance with the specified climb
profile unless cleared by ATC.

**ROUTING/ALTITUDE**

SSN01 (900'+; K200-) - SSE02 (K200-) - SSE05 (K200-) - SSS11 (3000'+; K250-) - SSS12 (K250-) - SSS18 (5000'; K250-) - GAMDO (K250-) - DET (K250-) - DVR (K250-).



NOISE MONITORING TERMINAL/NAME/LOCATION			ELEVATION ABOVE AERODROME	ADJUSTMENT db(A)
3	Howe Green School, Great Hallingbury	N51 50.8 E000 11.5	- 21m	- 1.0
4	Thames Water, Bishop's Stortford	N51 51.3 E000 10.7	- 36m	- 1.4
5	Woolcott Restaurant, Great Hallingbury	N51 50.9 E000 10.9	- 26m	- 1.4
6	Morley, Woodside Green	N51 50.8 E000 11.9	- 26m	- 1.1
8	Anglian Water, Broxted	N51 54.9 E000 17.5	- 16m	- 0.6
9	Moor End Farm, Broxted	N51 54.6 E000 17.9	- 16m	- 0.8
10	Goodacres, Broxted	N51 55.1 E000 17.4	9m	+ 0.2
11	Chickney Hall Villas, Broxted	N51 55.5 E000 17.3	-15m	-1.3


If the aircraft was required to take-off with a tailwind an amount of the noise recorded at the noise monitor should be disregarded.

Tailwind component	≤1 KT	≤2 KT	≤3 KT	≤4 KT	> 4 KT
Amount to be disregarded	0.4 dB	0.8 dB	1.2 dB	1.6 dB	2.0 dB

EGSS/STN
Apt Elev 348'
N51 53.1 E000 14.1

JEPPesen
13 SEP 13 (30-9)

LONDON, UK
STANSTED



ADDITIONAL RUNWAY INFORMATION

ADDITIONAL RUNWAY INFORMATION						USABLE LENGTHS		TAKE-OFF	WIDTH	
RWY						LANDING BEYOND				
						Threshold	Glide Slope			
04	②	HIRL (60m) CL (15m) HIALS-II TDZ PAPI-L (3.0°)	③	RVR	9016'	2748m	7983'	2433m	⑤	151' 46m
22		HIRL (60m) CL (15m) HIALS-II TDZ PAPI-L (3.0°)	④	RVR			8970'	2734m		

② Runway grooved. ③ HSTIL-PR & QR ④ HSTIL-NR & LR

⑤ TAKE-OFF RUN AVAILABLE

RWY 04:

From rwy head	9993' (3046m)
hold posn K1	9252' (2820m)
hold posn L1	7890' (2405m)
hold posn V1	6017' (1834m)

RWY 22:


From rwy head	10,003' (3049m)
hold posn Q1	8816' (2687m)
hold posn P3	7687' (2343m)
hold posn U	6076' (1852m)

Standard

TAKE-OFF ①

	LVP must be in Force				
	Approved Operators HIRL, CL & mult. RVR req	RL, CL & mult. RVR req	RL & CL	RCLM (DAY only) or RL	RCLM (DAY only) or RL
A					
B	125m	150m	200m	250m	400m
C					
D	150m	200m	250m	300m	500m

① Operators applying U.S. Ops Specs: CL required below 300m; approved HUD required below 150m.




HOT SPOTS

(For information only, not to be construed as ATC instructions.)

- HS1** Two runway entry points in close proximity.
- HS2** Western Apron - potential conflict with vehicles.
CAT III holding position W3 is adjacent an airside road.
- HS3** Traffic vacating the runway has priority.
Potential for acft conflict in this area, to and from the runway.

INS COORDINATES			
STAND No.	COORDINATES	STAND No.	COORDINATES
1 thru 2	N51 53.2 E000 15.2	76	N51 53.8 E000 15.5
3 thru 8	N51 53.2 E000 15.1	83L thru 84R	N51 53.7 E000 15.7
9, 9L, 9R	N51 53.3 E000 15.0	85L, 85R	N51 53.8 E000 15.6
10	N51 53.2 E000 15.3	204, 204F, 204L	N51 53.0 E000 14.7
11, 11L	N51 53.3 E000 15.2	204R	N51 53.1 E000 14.7
11R	N51 53.3 E000 15.3	205	N51 53.1 E000 14.6
12, 12L, 12R	N51 53.3 E000 15.2	205L	N51 53.1 E000 14.7
13, 13L	N51 53.3 E000 15.1	205R	N51 53.1 E000 14.6
13R	N51 53.3 E000 15.2	213	N51 53.1 E000 14.8
14L	N51 53.4 E000 15.1	213L	N51 53.1 E000 14.7
14R	N51 53.3 E000 15.1	213R	N51 53.1 E000 14.8
15	N51 53.4 E000 15.1	214, 214L, 214R	N51 53.1 E000 14.7
20	N51 53.4 E000 15.4		
21 thru 23L	N51 53.4 E000 15.3		
23R	N51 53.4 E000 15.2		
24	N51 53.5 E000 15.2		
24L	N51 53.4 E000 15.2		
24R	N51 53.5 E000 15.2		
25	N51 53.5 E000 15.1		
30 thru 32	N51 53.4 E000 15.4		
32L	N51 53.4 E000 15.3		
32R	N51 53.4 E000 15.4		
33, 33L	N51 53.5 E000 15.3		
33R	N51 53.4 E000 15.3		
34	N51 53.5 E000 15.3		
34L	N51 53.5 E000 15.2		
34R	N51 53.5 E000 15.3		
40 thru 42R	N51 53.5 E000 15.5		
43, 43L, 43R	N51 53.5 E000 15.4		
44, 44L, 44R	N51 53.6 E000 15.4		
45L	N51 53.6 E000 15.3		
45R	N51 53.5 E000 15.3		
50, 50L, 50R	N51 53.5 E000 15.6		
51, 51L	N51 53.5 E000 15.5		
51R	N51 53.5 E000 15.6		
52, 52L, 52R	N51 53.6 E000 15.5		
53L, 53R	N51 53.6 E000 15.4		
61, 61L	N51 53.5 E000 15.7		
61R thru 62L	N51 53.6 E000 15.7		
62R thru 63L	N51 53.6 E000 15.6		
63R, 64L	N51 53.7 E000 15.6		
64R, 65L	N51 53.7 E000 15.5		
65R	N51 53.6 E000 15.4		
70, 70L	N51 53.6 E000 15.7		
70R	N51 53.6 E000 15.8		
71, 71L, 71R	N51 53.6 E000 15.7		
72, 72L	N51 53.7 E000 15.6		
72R	N51 53.7 E000 15.7		
73, 73L, 73R	N51 53.7 E000 15.6		
74	N51 53.7 E000 15.5		



INS COORDINATES

STAND No.	COORDINATES	STAND No.	COORDINATES
501	N51 52.9 E000 13.3	515	N51 53.3 E000 13.2
502	N51 52.8 E000 13.3	516	N51 53.2 E000 13.2
503, 504	N51 52.9 E000 13.5	517	N51 53.3 E000 13.1
505 thru 507	N51 53.0 E000 13.6	518	N51 53.2 E000 13.1
508	N51 53.0 E000 13.7	519	N51 53.1 E000 13.0
509, 510	N51 53.1 E000 13.7		
511	N51 53.2 E000 13.6		
512	N51 53.2 E000 13.5		
513	N51 53.2 E000 13.4		
514	N51 53.3 E000 13.3		

STRAIGHT-IN RWY		DA(H) / MDA(H)	RVR (ALS/ALS out)
04	CAT 2 ILS DME	432' (100')	RA 108' - 300m
	ILS DME	532' (200')	500m / 1000m
	LOC	670' (338')	800m / 1000m
	SRA	960' (628')	1000m / 1000m
22	CAT 2 ILS DME	448' (100')	RA 101' - 300m
	ILS DME	548' (200')	500m / 1000m
	LOC	740' (392')	800m / 1000m
	SRA	970' (622')	1000m / 1000m

CIRCLE-TO-LAND ①	MDA(H)	VIS
	830' (482') ②	1000m

① Rwy 04: See 30-4 noise abatement.


② After SRA 04: 960' (612').

After SRA 22: 970' (622').


TAKE-OFF RWY 04, 22				
LVP must be in Force ③				
RL, FATO LTS, CL & RVR info	RL, FATO LTS & RCLM	Unlit/unmarked defined RWY/FATO	Nil Facilities DAY	Nil Facilities NIGHT
150m	200m	200m	250m ④	800m



③ Without LVP 400m are stipulated.


④ Or rejected take-off distance whichever is the greater.



BRIEFING STRIP™

ATIS		ESSEX Radar (APP)		STANSTED Tower		*Ground			
127.17		114.55		120.62		123.8		121.72	
LOC ISED *110.5		Final Apch Crs 044°		GS D4.0 ISED 1660' (1328')		CAT II & IIIA ILS Refer to Minimums		Apt Elev 348' RWY 332'	
MISSED APCH: Climb STRAIGHT AHEAD to not above 3000'. At D2.0 ISED turn LEFT onto R-104 inbound. Cross D5.0 BKY at 3000', then continue to VOR at 3000', or as directed. MAX 185 KT until established on R-104. Missed apch climb gradient of 4.9% may be required to ensure CAS containment. Acft unable to receive VOR, inform ATC.									
Alt Set: hPa		Rwy Elev: 12 hPa		Trans level: By ATC		Trans alt: 6000'			
1. Special Aircrew and Acft Certification Required. 2. ILS DME reads zero at rwy 04 displ threshold.									






Gnd speed-Kts	70	90	100	120	140	160		MAX 185 KT	Not above 3000'	D2.0 ISED
GS	3.00°	377	485	539	647	755				

Standard		STRAIGHT-IN LANDING RWY 04	
CAT IIIA ILS		CAT II ILS	
DH 50'		ABCD RA 108' DA(H) 432' (100')	
RVR 200m		RVR 300m I	

I Operators applying U.S. Ops Specs: Autoland or HUD required below RVR 350m.

BRIEFING STRIP™

ATIS		ESSEX Radar (APP)		STANSTED Tower		*Ground			
127.17		114.55		120.62		123.8		121.72	
LOC ISX *110.5		Final Apch Crs 224°		GS D4.0 ISX 1670' (1322')		ILS DA(H) 548' (200')		Apt Elev 348' RWY 348'	
MISSED APCH: Climb STRAIGHT AHEAD to not above 3000'. At D3.1 ISX turn RIGHT onto R-174 inbound at D8.0 BKY, continue climb as necessary to VOR at 3000', or as directed.									
MAX 185 KT until established on R-174. Acft unable to receive VOR, inform ATC.									
Alt Set: hPa		Rwy Elev: 13 hPa		Trans level: By ATC		Trans alt: 6000'			
ILS DME reads zero at rwy 22 threshold.									






Gnd speed-Kts	70	90	100	120	140	160	HIALS-II PAPI	MAX 185 KT	Not above 3000'	D3.1 ISX
ILS GS or LOC Desc Angle 3.00°	377	485	539	647	755	862				
MAP at D0.5 ISX										

PANS OPS 4	Standard STRAIGHT-IN LANDING RWY 22 ILS				CIRCLE-TO-LAND			
	LOC (GS out) CDFA							
	DA(H) 548' (200')			DA/MDA(H) 740' (392')				
	FULL	Limited	ALS out	ALS out	Max Kts	MDA(H)	VIS	
	A				100	830' (482')	1500m	
B				RVR 1500m	135	850' (502')	1600m	
C	RVR 550m	RVR 750m	RVR 1200m		180	1020' (672')	2400m	
D				RVR 1800m	205	1050' (702')	3600m	

■ Rwy 04: See 30-4 noise abatement.

BRIEFING STRIP

ATIS		ESSEX Radar (APP)		STANSTED Tower		*Ground			
127.17		114.55		120.62		123.8		121.72	
LOC ISX *110.5		Final Apch Crs 224°		GS D4.0 ISX 1670' (1322')		CAT II & IIIA ILS Refer to Minimums		Apt Elev 348' RWY 348'	
MISSED APCH: Climb STRAIGHT AHEAD to not above 3000'. At D3.1 ISX turn RIGHT onto R-174 inbound at D8.0 BKY, continue climb as necessary to VOR at 3000', or as directed.								 MSA ARP	
MAX 185 KT until established on R-174. Acft unable to receive VOR, inform ATC.									
Alt Set: hPa		Rwy Elev: 13 hPa		Trans level: By ATC		Trans alt: 6000'			
1. Special Aircrew and Acft Certification Required. 2. ILS DME reads zero at rwy 22 threshold.									



Gnd speed-Kts	70	90	100	120	140	160	HIALS-II		MAX	Not above	D3.1 ISX
GS	3.00°	377	485	539	647	755	PAPI		185 KT	3000'	

Standard		STRAIGHT-IN LANDING RWY 22	
CAT IIIA ILS		CAT II ILS	
DH 50'		ABCD RA 101' DA(H) 448' (100')	
RVR 200m		RVR 300m	

Operators applying U.S. Ops Specs: Autoland or HUD required below RVR 350m.




Chart changes since cycle 26-2013

ADD = added chart, REV = revised chart, DEL = deleted chart.

ACT	PROCEDURE IDENT	INDEX	REV DATE	EFF DATE
LONDON, (STANSTED - EGSS)				

TERMINAL CHART CHANGE NOTICES

Chart Change Notices for Airport EGSS

Type: Terminal

Effectivity: Temporary

Begin Date: Immediately

End Date: Until Further Notice

(30-3P/30-3Q) Eff 2 May 13 Trial RNP1 SIDs CLN 1E and DVR 1D established, refer to temp charts and latest NOTAMs.

Type: Terminal

Effectivity: Temporary

Begin Date: Immediately

End Date: Until Further Notice

(30-2B thru 30-2G, 30-2S thru 30-2X, 30-3H thru 30-3N) MSA based on ARP lowered btn 270°-360° inbound to 1700'.